



Oil & Gas Industry

# PROJECT: (2) FABRICATED VFD BUILDINGS

Customer: Dearing Compressor and Pump • Dimensions (Each): 14'- 0" W x 52'-6" L x 13'-0" H



- Structural base to hold an excess of 70,000 lbs. of electrical equipment
- Integrated wireway channel in base structure to run medium voltage cables between drives
- Bottom-entry cable access for incoming and outgoing power terminations







- Fully-welded, heavy-duty 11gauge steel wall and roof construction
- Two-piece removable roof sections for electrical equipment installation in field
- Rear-access coverplates for bus-bar connections in field
- Pre-fabricated supply and return openings for air handler connections

Panelmatic ensures that all work is completed by certified welders, certified technicians



We are experts in the following services

- Analyzers
- Analyzer Shelters (CEMS)
- Compressor Panels
- Control Houses
- Custom Consoles
- Custom Fabrication
- Custom Tubing
- Custom Control Panels
- DCS Cabinets
- Heat Trace Panels
- Interposing Relay Panels
- Marshalling Panels
- Modified Shipping Containers for Controls
- Modified Shipping Containers for Storage/Office
- Motor Control Center (MCC)
- Panels/Houses for Hazardous Locations
- Pneumatic Panels
- Power Distribution Centers (PDC)
- Power Relay Panels
- Remote Instrument Enclosures (RIE)
- Shutdown Systems
- Transmitter Racks
- UPS Cabinets
- Wind Power



Visit [www.panelmatic.com](http://www.panelmatic.com) for contact information



ISO-9000  
(BASED)

